

WHY CHOOSE READYMADE?



LOCATION: NYC/METRO AREA

Unlike all competition, we can be on site for same day service.

UL LISTED: FILE#: E521314

Quality under the watchful eye of U.L.

TRAINING IN THE FIELD

We visit the site to confirm prefab package works as ordered.

EFFICIENT DELIVERY SYSTEM

Cages on wheels that fit through all doors. Pallet deliveries that fit through doors are also available

UNIQUE ELECTRICAL INSTALLS

Never open a box! All splices terminated and tested. 1 Man electrical panel install

FLEXIBILITY & SAVINGS

Prefab labor only option (*material provided by the client*)
Can sell a complete bundled package (*labor and material*) Savings on Material.

DRAWINGS/ENGINEERING

Easy to read and follows code

COLOR CODED LABELING SYSTEM

Extremely easy to read and laid out. Any helper or apprentice can do it

ReadyMadeElectric.com



READYMADE
ELECTRICAL PRE FAB SYSTEM

**MADE BY
ELECTRICIANS
FOR
ELECTRICIANS**



NYC/METRO AREA

Unlike all competition, we can be on site for same day service.



EMAIL

info@ReadyMadeElectric.com



WEBSITE

www.readymadeelectric.com

ReadyMadeElectric.com

IN WALL ROUGH-IN

Residential / Commercial / Health Care Facility

- Prefabricated boxes with Devices pre-wired
- Sent with Metal Protective Covers
- Color Coded Labels by room with Circuit # and Box ID. **Never open a box!**

PANEL BUILDS

Commercial Panels

- Pre-Wired Panel with Trough assembly on top or bottom
- Conduit Nipples and Fittings based on Job Spec
- Wires Labeled with Circuit #
- Ships Complete on Unistrut or Plywood

Residential Panels

- Pre-Wired Load Centers with cables cut to length - MC or Non-Metallic Cable
- Labeled & Color Coded by Room
- Ships Complete with Metal Angle Brackets for pre-set sheetrock size
- Fits directly into studs

CONDUIT

Conduit Bends

- EMT - ½" to 4"
- RMC - ½" to 4"
- Conduit Stub Ups w/ Drag String

Conduit Threading

- RMC - ½" to 4"

PVC Conduit Bending

- PVC Duct Bank

UNISTRUT TRAPEZES

Unistrut Racks

- Unistrut & Threaded Rod Cut to Length
- Tell us the dimensions and we will build it!
- Also consider ceiling supported J-Boxes!

TRANSFORMERS

Transformer - 15, 30, 45, 75, 112 KVA

- Unistrut Rack Assembly for easy hanging
- Complete Wiring & Torqued to Spec
- Assembled with Greenfield or Trough on either side

LIGHTING

High Hats/Surface Mount Lights

- Pre-Wired together - in packs
- Switch legs pre-wired in rough-in assembly system
- Protected with bubble wrap for delivery

WIRE HARNESSSES

Multi-Wire Branch Circuits Harnesses

Conduit Runs

- THHN paralleled on a Reel, Labeled with Circuit # multiple times on both ends

MC Harnesses

- MC Cable Paralleled on a Reel, Labeled with Circuit # Multiple times on both ends

LOW VOLTAGE

Cat6 / Coax Cable

- Cut to length, Labeled, Terminated & Tested
- NID Box Assembly on Metal Angle Brackets
- Fits directly into studs
- Pre-set depth for sheetrock

SURFACE MOUNTED ELECTRICAL INSTALLS

- IDF Room Receptacle Power
- Wiremold Installations

TEMPORARY

Power

- Temporary Power GFCI Receptacle buckets pre-wired to a J-box for field connection
- Temporary Transformer Setups
- 480V & 208V Panels Mounted with a Transformer to Step up or Down Voltage

Lighting

- Romex Stringers cut to desired lengths with female cord ends for bright HighBay Fixtures



READYMADE
ELECTRICAL PRE FAB SYSTEM